




TOP OF METER BOX TO BE 3/4" ABOVE FINISH GRADE IN PARKWAYS, AND FLUSH WITH SURFACE OF SIDEWALKS, IN SIDEWALK AREA.



STANDARD

ALTERNATE

WHEN APPROVED BY DEPT. OF PUBLIC WORKS.




ALTERNATE - IF WALK CONTIGUOUS WITH CURB NO SCALE

GENERAL NOTES:

1. SEE WATER SERVICE STANDARD DRAWINGS FROM MAIN TO PROPERTY LINE. COORDINATE INSTALLATION WITH CITY DEPT. OF PUBLIC WORKS, SO METER BOX CAN BE SET TO FINAL GRADE.
2. COMPLY WITH CITY OF SANTA MARIA STANDARD SPECIFICATION FOR MATERIALS & INSTALLATION OF WATER MAINS.

- ① METER BOX FIBERLITE OR ARMORCAST. USE FL-12 FOR 3/4" & 1" METERS. USE FL-36 FOR 1-1/2" AND 2" METERS. FOR METERS PROVIDING DOMESTIC AND FIRE SPRINKLER SERVICE, SEE STANDARD DRAWINGS.
- ② USE ONE-PIECE METAL LID FOR TRAFFIC CONDITIONS, USE ONE-PIECE FIBER LITE OR OTHER APPROVED LIGHTWEIGHT MATERIAL FOR ALL OTHER CONDITIONS; INCLUDE PROBE HOLE ON ALL LIDS AND MARKED "WATER".
- ③ COMMON BRICK ONE ROW, PLACED FULL LENGTH AND UNDER BOX WALLS ONLY FOR 3/4", 1" AND 1-1/2" METERS; THREE ROWS OF BRICKS REQUIRED FOR 2" METERS.

RICHARD G. SWEET R.C.E. 44,213 EXP. 6/30/07		DATE 11/22/04			City of Santa Maria Standard Drawing	
REVISIONS		BY	APP		DATE	DESCRIPTION:
A	NEW STD. No. ASSIGNED UTILITY DEPARTMENT REVISIONS	CJP JAS		6/1/12 9/7/17	WATER METER BOX (UP TO 2" METER)	WA-15A
DRAWN BY: R.L.B.		DATE DRAWN: 11/66		SCALE: NONE		SHEET 1 OF 1